Minute No. 620
Report - Standing Policy Committee on Property and Development - July 18, 2005

Item No. 2 **Subdivision and Rezoning - east side Main Street, north and south of Commonwealth Avenue (Coral-Reef Holdings Ltd.)**
File DASZ 11/2005

COUNCIL DECISION:

Council concurred in the recommendation of the Standing Policy Committee on Property and Development and adopted the following:

1. That the plan of subdivision proposed under File DASZ 11/2005 be approved for preparation as a plan of subdivision by a Manitoba Land Surveyor in accordance with revised Schedule "A" for File DASZ 11/2005 dated June 16, 2005, for registration in the Winnipeg Land Titles Office subject to the following:

    A. That the Developer be required to enter into a Development Agreement with the City containing all the conditions outlined in the report of the Administrative Coordinating Group dated May 31, 2005, with the following amendments:

        i. That the Developer's responsibilities in clauses 1. a) and b) be limited to those traffic improvements that have not yet been installed.

        ii. That clause 2 be deleted in its entirety and the remaining clauses renumbered accordingly.

        iii. That in former clause 13, add the words "prior to the issuance of any occupancy permits for the site" after the words "The Developer shall ensure that".

        iv. That former clause 18 be deleted and replaced with the following new clause numbered as 17, and the remaining clauses renumbered accordingly, namely:

            "17. The Developer shall dedicate the river bottom forest, as shown on revised Schedule "A" dated June 16, 2005, as Public Open Space, the area of which is approximately eight per cent (8%) of the land within the proposed subdivision, and shall pay cash in lieu of landscaping and servicing that open space in accordance with City policy".

Report - Standing Policy Committee on Property and Development - July 18, 2005

COUNCIL DECISION (continued)

v. That a new clause be added as number 20, namely:

"20. The Developer's responsibility for trail development within the river bottom forest area be limited to the cost of developing a low impact natural trail to be designed in consultation with and to the approval of the City Naturalist and located below the elevation of the crest of the dike".

2. That the Director of Planning, Property and Development be authorized to certify any documents in connection therewith.

3. That The Winnipeg Zoning By-Law No. 6400/94 be amended by rezoning the subject land as shown on revised Schedule "A" for File DASZ 11/2005 dated June 16, 2005, to an "R1-4" Residential District and a "PR1" Parks and Recreation District.

4. That in the event the application is not proceeded with expeditiously and the by-law is not enacted within twenty-four (24) months after adoption of the report by Council, the matter shall be deemed to be concluded and shall not be proceeded with unless an extension of time is applied for prior to the expiry of this twenty-four (24) month period and the extension is subsequently approved by Council.

5. That the City Solicitor/Manager of Legal Services be requested to prepare the necessary by-law in accordance with the above.

6. That the subdivision section of the by-law shall come into force and effect upon execution by the City of Winnipeg of the Development Agreement.

7. That the zoning section of the by-law shall come into force and effect when the Plan of Subdivision has been registered in the Winnipeg Land Titles Office provided that the said effective date occurs within twenty-four (24) months from the date that the said rezoning by-law is adopted by Council.

8. That the Plan of Subdivision shall be submitted for the approval of the Director of Planning, Property and Development within two (2) years of the date of passage of the aforementioned by-law.

Report - Standing Policy Committee on Property and Development - July 18, 2005

COUNCIL DECISION (continued)

9. That in the event the necessary City of Winnipeg mylar approval signatures have not been secured within twenty-four (24) months after adoption of the by-law, the matter shall be deemed to be concluded and shall not be proceeded with unless Council extends that time.

Report - Standing Policy Committee on Property and Development - July 18, 2005

DECISION MAKING HISTORY:

Moved by Councillor De Smedt,

That the recommendation of the Standing Policy Committee on Property and Development be adopted by consent.

Carried

EXECUTIVE POLICY COMMITTEE RECOMMENDATION:

On July 20, 2005, the Executive Policy Committee concurred in the recommendation of the Standing Policy Committee on Property and Development and the Lord Selkirk-West Kildonan Community Committee, as amended, and submitted the matter to Council.

STANDING COMMITTEE RECOMMENDATION:

On July 18, 2005, the Standing Policy Committee on Property and Development concurred in the recommendation from the Lord Selkirk-West Kildonan Community Committee, with the following amendments, namely:

- That Recommendation 1.A.v. be deleted in its entirety.

- That in Recommendation 1.A.vi., the new clause be added as number 20,

and submitted the matter to the Executive Policy Committee and Council.

On July 5, 2005, the Standing Policy Committee on Property and Development laid over consideration of the matter to a special meeting of the Committee to be held on July 18, 2005, at 9:00 a.m. in the West Committee Room, Council Building, 510 Main Street and in the interim requested the Administration to review the recommendations from the Lord Selkirk –West Kildonan Community Committee as they relate to dedication and the deletion of various obligations and payments in light of the desire to preserve the river bottom forest area, and, to report back on the value of the additional river bank lands and the issue of compensation to the Developer.

COMMUNITY COMMITTEE RECOMMENDATION:

On June 16, 2005, the Lord Selkirk-West Kildonan Community Committee did not concur in the administrative recommendation (for an adjournment) and recommended that the application for subdivision and rezoning under File DASZ 11/2005 be approved, subject to conditions of approval outlined in the report of the Manager of Planning and Land Use dated June 6, 2005, with the following amendments, namely:

Report - Standing Policy Committee on Property and Development - July 18, 2005

DECISION MAKING HISTORY (continued)

COMMUNITY COMMITTEE RECOMMENDATION (continued)

Report of the Manager of Planning and Land Use:

- That in recommendation 1, the word "revised" be added in front of the words "Schedule A" and the date of the Schedule "A" be changed to read "June 16, 2005".

- That in recommendation 3, the word "revised" be added in front of the words "Schedule A" and the date of the Schedule "A" be changed to read "June 16, 2005".

- That in recommendation 8, the words "approved and signed by" be replaced with the words "submitted for the approval of".

Report of the Administrative Coordinating Group

- That the Developer's responsibilities in clauses 1. a) and b) be limited to those traffic improvements that have not yet been installed.

- That clause 2 be deleted in its entirety and the remaining clauses renumbered accordingly.

- That in former clause 13, add the words "prior to the issuance of any occupancy permits for the site" after the words "The Developer shall ensure that".
- That former clause 18 be deleted and replaced with the following new clause numbered as 17, and the remaining clauses renumbered accordingly, namely:

  "17. The Developer shall dedicate the river bottom forest, as shown on revised Schedule "A" dated June 16, 2005, as Public Open Space, the area of which is approximately 8% of the land within the proposed subdivision, and shall pay cash in lieu of landscaping and servicing that open space in accordance with City policy".

- That former clause 20 be deleted in its entirety.

Report – Standing Policy Committee on Property and Development – July 18, 2005

DECISION MAKING HISTORY (continued):

COMMUNITY COMMITTEE RECOMMENDATION (continued):

- That a new clause be added as number 19, namely:

  "19. The Developer's responsibility for trail development within the river bottom forest area be limited to the cost of developing a low impact natural trail to be designed in consultation with and to the approval of the City Naturalist and located below the elevation of the crest of the dike".

and submitted its recommendation to the Standing Policy Committee on Property and Development.

On June 14, 2005, the Lord Selkirk-West Kildonan Community Committee adjourned the public hearing to June 16, 2005, at 9:00 a.m. in the North Committee Room, Council Building.

RE: **Subdivision and Rezoning - east side Main Street, north and south of Commonwealth Avenue (Coral-Reef Holdings Ltd.)**
File DASZ 11/2005

For submission to: **The Standing Policy Committee on Property and Development**

Prepared by: **Diane Timmins, Clerk,**
Lord Selkirk-West Kildonan Community Committee

Report date: **June 29, 2005**

COMMUNITY COMMITTEE RECOMMENDATION:

On June 14, 2005, the Lord Selkirk-West Kildonan Community Committee did not concur in the administrative recommendation and recommends to the Standing Policy Committee on Property and Development:

The Lord Selkirk-West Kildonan Community Committee did not concur in the administrative recommendation and recommends to the Standing Policy Committee on Property and Development:

1. That the plan of subdivision proposed under File DASZ 11/2005 be approved for preparation as a plan of subdivision by a Manitoba Land Surveyor in accordance with ***revised*** Schedule "A" for File DASZ 11/2005 dated ***June 16, 2005***, for registration in the Winnipeg Land Titles Office, subject to the following:

    A. That the Developer be required to enter into a Development Agreement with the City containing all the conditions outlined in the report of the Administrative Coordinating Group dated May 31, 2005, ***with the following amendments:***

        i. That the Developer's responsibilities in clauses 1. a) and b) be limited to those traffic improvements that have not yet been installed.

        ii. That clause 2 be deleted in its entirety and the remaining clauses renumbered accordingly.

        iii. That in former clause 13, add the words "prior to the issuance of any occupancy permits for the site" after the words "The Developer shall ensure that".

        iv. That former clause 18 be deleted and replaced with the following new clause numbered as 17, and the remaining clauses renumbered accordingly, namely:

"17. The Developer shall dedicate the river bottom forest, as shown on revised Schedule "A" dated June 16, 2005, as Public Open Space, the area of which is approximately 8% of the land within the proposed subdivision, and shall pay cash in lieu of landscaping and servicing that open space in accordance with City policy".

v. That former clause 20 be deleted in its entirety.

vi. That a new clause be added as number 19, namely:

"19. The Developer's responsibility for trail development within the river bottom forest area be limited to the cost of developing a low impact natural trail to be designed in consultation with and to the approval of the City Naturalist and located below the elevation of the crest of the dike".

2. That the Director of Planning, Property and Development be authorized to certify any documents in connection therewith.

3 That The Winnipeg Zoning By-Law No. 6400/94 be amended by rezoning the subject land as shown on ***revised*** Schedule "A" for File DASZ 11/2005 dated ***June 16, 2005***, to an "R1-4" Residential District and a "PR1" Parks and Recreation District.

4. That in the event the application is not proceeded with expeditiously and the by-law is not enacted within twenty-four (24) months after adoption of the report by Council, the matter shall be deemed to be concluded and shall not be proceeded with unless an extension of time is applied for prior to the expiry of this twenty-four (24) month period and the extension is subsequently approved by Council.

5. That the City Solicitor/Manager of Legal Services be requested to prepare the necessary by-law in accordance with the above.

6. That the subdivision section of the by-law shall come into force and effect upon execution by the City of Winnipeg of the Development Agreement.

7. That the zoning section of the by-law shall come into force and effect when the Plan of Subdivision has been registered in the Winnipeg Land Titles Office provided that the said effective date occurs within twenty-four (24) months from the date that the said rezoning by-law is adopted by Council.

8. That the Plan of Subdivision shall be ***submitted for the approval of*** the Director of Planning, Property and Development within two (2) years of the date of passage of the aforementioned by-law.

9. That in the event the necessary City of Winnipeg mylar approval signatures have not been secured within twenty-four (24) months after adoption of the by-law, the matter shall be deemed to be concluded and shall not be proceeded with unless Council extends that time.

Note: The wording in bold and italics denotes amendments made by the Community Committee.

The Lord Selkirk-West Kildonan Community Committee provided the following supporting reasons for its recommendation:

1. The proposed development is infill housing which Plan Winnipeg encourages and will assist in addressing the shortage of serviced land in the City.

2. The proposed development has unusual costs which no other development in this part of the City has had to incur and the proposed amendments to the report of the Administrative Coordinating Group seek to mitigate some of those costs to make it fair for both sides.

3. There is minimal opposition to this application.

PUBLIC HEARING SUMMARY


File: DASZ 11 /2005

Before: Lord Selkirk-West Kildonan Community Committee
Councillor O'Shaughnessy, Chairperson
Councillor Lazarenko
Councillor Pagtakhan

Public Hearing: June 14, 2005
June 16, 2005
Council Building, 510 Main Street

Applicant: Lombard North Group (1984) Ltd.
(David Palubeski)

Subject:



APPLICANT : LOMBARD NORTH GROUP
FILE : DASZ 11/05
PROPOSAL : An application for the approval of the plan of subdivision shown outlined above as may be determined by Council and for a proposed zoning change to By-law No. 6400/94 by rezoning the land shown outlined above from an "R1-20" RESIDENTIAL DISTRICT to a "PR1" PARKS AND RECREATION DISTRICT and an "R1-4" RESIDENTIAL DISTRICT. **For information, phone Mr. M. Robinson, Planner at 986-3213.**

Premises Affected: east side Main Street, north and south of Commonwealth Avenue

Exhibits Filed:

1. Revised Application dated May 25, 2005
2. Notification of Public Hearing dated May 26, 2005
3. Manitoba Status of Titles 1611307, 1296409, 1245827, 2067489

4a Letter of authorization dated February 24, 2005, from Coral-Reef Holdings Ltd. to Lombard North Group (1984) Ltd.

4b. Letter of authorization dated April 18, 2005, from Coral-Reef Holdings Ltd. to Lombard North Group (1984) Ltd.

4c. Letter of authorization dated November 24, 2004, from B.D.B. Enterprises Ltd. to Greenview Homes (Manitoba) Ltd.
5. Proposed development Lot Width and Area Calculations dated May 19, 2005
6. Plan showing proposed Coral-Reef subdivision dated May 19, 2005
7. Communication dated April 28, 2005, from R. P. Victoruk with respect to the application
8. Communication dated June 7, 2005, from Margaret Reda in opposition to the application
9. Communication dated June 10, 2005, from Karen Jones in opposition to the application
10. Report from the Manager of Planning and Land Use dated June 6, 2005
11. Report from the Administrative Coordinating Group dated May 31, 2005
12. Communication dated June 14, 2005, from Jacques Tardif, Canada Research Chair in Dendrochronology, Centre for Forest Interdisciplinary Research, University of Winnipeg, in opposition to the application
13. Inspection Report
14. Communication dated June 14, 2005, from John Whiteway in support of the application, submitted by David Palubeski at the public hearing on June 14, 2005
15. Communication dated June 14, 2005, from Carol Lehmann in support of the application, submitted by David Palubeski at the public hearing on June 14, 2005
16. Communication dated June 14, 2005, from David Palubeski, President, Lombard North Group (1984) Ltd., outlining the Developer's response to the ACG proposals for amending the plan of subdivision, submitted at the public hearing on June 14, 2005
17. Amended Plan of Subdivision for DASZ 10/2005 dated June 10, 2005, submitted by David Palubeski, President, Lombard North Group (1984) Ltd., at the public hearing on June 14, 2005
18. Presentation of Christine Common-Singh on behalf of The Coalition to Save the Elms, in opposition to the application submitted at the public hearing on June 14, 2005
19. Presentation and photographs submitted by Lisa Kazmerik in opposition to the application submitted at the public hearing on June 14, 2005

REPRESENTATIONS:

In Support:

Baldev S. and Paramjit Bedi
Ric Carrgon
Carol and Werner Lehmann
Ross Mitchell
David Palubeski, Lombard North Group (1984) Ltd.
Brenda L. Rosney
Bob and Anita Victoruk
John Whiteway

In Opposition:

Christine Common Singh, on behalf of the Coalition to Save the Elm
Karen Jones
Michele Kading
Lisa Kazmerik
Margaret Reda
Robert Snyder
Jacques Tardif, Canada Research Chair in Dendrochronology,
Centre for Forest Interdisciplinary Research, University of Winnipeg

For Information:

Moira Cole
Betty Ann and Richard Graydon
Douglas W. Machan
M. J. Mouser

For the City:

Mr. D. Marsh, Planner, Planning, Property and Development Department
Mr. M. Robinson, Planner, Planning, Property and Development Department
Mr. E. Carriere, Land Development Engineer, Planning, Property and Development Department
Mr. D. Kingerski, Riverbank Management Engineer, Planning, Property and Development Department
Ms C. Heming, City Naturalist, Public Works Department
Mr. G. Mohr, Land Drainage Planning Engineer, Water and Waste Department

SUMMARIZATION OF REPRESENTATIONS AND SUBMISSIONS
MADE AT THE PUBLIC HEARING

June 14, 2005
David Palubeski, on behalf of Lombard North Group (1984) Ltd. appeared in support of the application and indicated he would be speaking to the applications under File Nos. DASZ 10/2005 and DASZ 11/2005 concurrently. Committee was advised the applicant was representing three interests with the two subject applications, namely, the Seven Oaks School Division (for the proposed high school), Greenview Homes (Manitoba) Ltd., and Coral-Reef Holdings Ltd. Mr. Palubeski also submitted two letters of support from the two adjoining property owners affected by the proposed development; namely, John Whiteway and Carol Lehmann, filed as Exhibits "14" and "15" respectively, which were read into the record. Mr. Palubeski emphasized the need for the proposed development to accommodate the future uses of these lands. With the aid of an overhead projector, Mr. Palubeski gave an overview of the proposed development, and read into the record his presentation filed as Exhibit "16".

Committee was also advised "River Ridge" is the name that has been given to the area within Winnipeg north of the Chief Peguis Trail, on the east side of Main Street, south of Rivergrove Drive and is the name of this subdivision. It also represents the last piece of vacant land along the river on North Main Street and an opportunity for infill development. He stated that the land covered under File DASZ 11/2005 is the land located north of the Greenview lands and the proposed high school. Mr. Palubeski stated that prior to this public hearing, two public open houses were held where over 300 area residents attended the first open house and 100 at the second one. As a result of these open houses, community input was obtained in terms of the planning direction of the proposed development, and the applicant made adjustments to the original plan of subdivision. Additionally, in an effort to reconcile the City's wants in terms of dedication, while not compromising the potential economics of the project, an amended plan of subdivision was compiled, which Mr. Palubeski submitted and has been filed as Exhibit "17". He also advised that the amended plan received the support of the majority of the area residents who attended the second public open house and were supportive of the proposed development. He further noted that in the amended plan, the open space dedication was increased from 7.1 acres to 9.8 acres, composed entirely of river bottom forest area, and that the location of the dike was moved further away from the river. Accordingly, the total dedication under DASZ 10/2004 will be 24% of Greenview's property (excluding the school site). Mr. Palubeski also stated that only nine (9) of the large cottonwood trees would be impacted by the proposed development, but that the amended plan would preserve the majority of the river bottom forest. In answer to Committee's question with respect to riverbank stabilization works, Mr. Palubeski stated that according to their engineer's report, with the relocation of the dike further away from the river, that if the erosion that has occurred as it has in the last fifty years continues for the next 100 years at the same rate, they would have a hundred year safety margin before the tow of the dike became an issue in terms of erosion protection. Mr. Palubeski further stated that his client requests that they be excluded from providing riverbank rip-rap for this development, but would be agreeable to contributing to same if the City provided lands in exchange for the additional park area they would provide. In this connection, Mr. Palubeski made specific reference to the

lands owned by the City on Red River Boulevard. Mr. Palubeski also stated that his clients' agreement to consider providing the additional river bottom forest and open space dedication is offered with the expectation that the City would provide credits under the Development Agreement to re-balance the financial impact of dedication of the project.

With respect to the administrative recommendation for an adjournment, Mr. Palubeski requested Committee to not concur in the request, and stated the opinion that an adjournment would only serve to delay the proposed project, and more importantly, delay the construction of the high school which is slated for opening in September 2007. He also stated that they have made every effort to work with the Administration in finding a creative solution to the unresolved issues. In response to Committee's question as to the level of funding being provided by the Seven Oaks School Division for the proposed development, Mr. Palubeski responded that with the construction of the high school, the community will benefit from increased green space and expanded recreational opportunities, inasmuch as a running track, a soccer field, basketball and tennis courts are proposed with the high school, that would be available for the joint use of the community.

Mr. Palubeski stated concurrence in part with the recommendations outlined in the report of the Manager of Planning and Land Use (Exhibit "10") and the report of the Administrative Coordinating Group (Exhibit "11"), and went over the Developer's responses to the ACG proposals, as outlined in Exhibit "16", in return for amending the plan of subdivision for DASZ 10/2005.

Brian O'Leary, Superintendent, Seven Oaks School Division No. 10, also appeared in support of the application. He emphasized the need for approval to be given to the high school and confirmed that the School Division is aiming for final construction and occupancy no later than September 2007. He stated the proposed site is a good location for a high school., In response to Committee's question, Mr. O'Leary stated the high school will cost approximately 12,000,000, will be 97,000 sq. ft. in size and will include a large day care which will accommodate seventy-nine (79) infants and pre-schoolers.

Christine Common Singh, on behalf of the Coalition to Save the Elms, appeared in opposition to the application as long as certain conditions were not met. She advised Committee that the position of the Coalition is consistent with the position of the City Naturalist, namely, that the entire 6.5 acres of river bottom forest should be preserved as an intact eco-system which is of very high environmental value. Ms Singh read into the record her presentation, filed as Exhibit "18". She stated the Coalition had two recommendations; one for the short term and one for the long term, namely,

1. That the recommendation on this matter be adjourned in order that a meeting be convened with the developer, administrators, scientists and other interested parties to further examine what is required to facilitate the developer while, at the same time, ensuring the preservation of a priceless ecological treasure.

2. The Coalition wishes to initiate a process with the City with the objective of creating a legislative package, with carrots and sticks, which will serve as a clear guide to developers, to decision makers and to the public as to which ecological entities in the city are protected and which are not.

Robert Snyder, also appearing in opposition to the application, stated concern with respect to the addition of a collector street, Ridgecrest Avenue, off Main Street, and the resulting increase in traffic for the area.

Michele Kading, also appearing in opposition to the application, expressed disappointment that the Community Committee was not considering an adjournment of the application to allow the developer to continue negotiations with the City Administration, which in her opinion, has made very important points that ought to be resolved first. Ms Kading urged Committee to take steps to ensure that the entire river bottom forest was salvaged, and noted that it has been identified as a priority in Plan Winnipeg. She stated that as this is a unique and sensitive area, prone to flooding, it should not be developed. Ms Kading also stated there is an acre of forest that will be impacted by development under File DASZ 11/2005, and expressed concern regarding the loss of some trees where there is an eagle's nest on the property. She further stated it was unlikely that the eagle would return to nest in the future. Ms Kading indicated concurrence in the comments made by the Coalition to Save the Elms that we need to look creatively at alternatives and ways by which the Developer can be compensated so that the river bottom forest lands can be set aside.

Lisa Kazmerik, also appearing in opposition to the application, advised Committee that she lives in the Rivergrove area. She stated concurrence in the comments made by Christine Common Singh, on behalf of the Coalition to Save the Elms, and Michele Kading. She read into the record her presentation, filed as Exhibit "19", and expressed concern regarding the river bottom forest and how it is being threatened with the proposed development.

Karen Jones, also appearing in opposition to the application, expressed concern regarding the habitat loss that is recognized as the number one threat to biodiversity that would occur with approval of the proposed development. In tact river bottom eco systems are rare and the proposed development would threaten this eco system. She therefore requested that Community Committee not permit development that would threaten this eco system and contribute to further fragmentation of the river bottom habitat.

Moira Cole, appearing for information, stated that for the most part, she is in favour of the proposed development but requested clarification on the houses that will be going into the development and the side yard requirements with the "R1-4" zoning.

In rebuttal, Mr. Palubeski stated that the original plans provided 3.1 acres of river bottom forest but the amended plan increases that area to 4.9 acres of river bottom forest that would not be impacted by the dike or the tow of the dike. Mr. Palubeski also noted that the river bottom forest has been abandoned and not been looked after for years. He stated that with the proposed

development, the river bottom forest will be a City asset, be supervised and will become a valuable resource integrated into the community.

He further stated that the proposed "R1-4" zoning will provide the Developer with flexibility with regards to house sizes and make it more affordable for home buyers, not to mention that approval of the proposed development will address the shortage and unavailability of serviced land in the City.

With respect to the request for the adjournment, Mr. Palubeski reiterated that his clients do not want to have the application adjourned inasmuch as every effort with the Administration has been made to find a solution to unresolved issues.

In conclusion, Mr. Palubeski requested Committee to recommend approval of the amended plan of subdivision which he submitted (filed as Exhibit "17") and also requested Committee's support for the credits to the Developer that have been identified in Exhibit "16", which, in his opinion, are an innovative way and without cost to the City, to compensate the Developer for a major contribution towards preserving part of the natural area within the riverbank.

June 16, 2005
No further representations were heard at the adjourned public hearing inasmuch as public representations were concluded on June 14, 2005.

Exhibit "10" referred to in File DASZ 11/2005


Winnipeg

Planning, Property and Development Department Report

To the Lord Selkirk – West Kildonan Community Committee

Date: **June 6, 2005**
File: **DASZ 11/05**
Related Files: **DASZ 10/05**
Subject: **An application has been received from Dave Palubeski, Lombard North Group for approval of a plan of subdivision and related zoning change to Zoning By-Law No. 6400/94 by rezoning the subject lands from a "R1-20" Residential District to "R1-4" Residential District and "PR-1" Parks and Recreation District to allow for the creation of single family lots and public reserve land.**

Location: **East side Main Street, north and south of Commonwealth Avenue**



Applicant: **Lombard North Group c/o Dave Palubeski**
Owner: **Coral Reef**

Recommendation: **Adjournment**

Report Summary:

- **Application to create 85 single-family lots and .7 acres of public reserve land**
- **Proposal meets Plan Winnipeg policies infill development and compatible land use**
- **The following issues remain outstanding**
  1. **A second point of access cannot be provided until there is resolution with the easement across the road right of way.**
  2. **The plan of subdivision will require modification to accommodate a southern connection to the cul-de-sac to reduce the length**
  3. **The riverfront lot depths will require modification to accommodate the dike completely within the private lots – leaving no disturbances within the public reserve land.**
  4. **The dike cannot be extended to the north because adjacent property owners have not provided authorization. An alternative dike alignment wholly contained within the applicant's property is required.**
- **The recommendation is to adjourn to a future date to allow more time for resolution of outstanding issues**

Site Description

The subject site, which is undeveloped, is zoned "R1-20" Residential. The total site area is 17.3 acres.

North: To the immediate north is the River Grove subdivision, which is fully developed and contains a mix of "R1-5" and "R1-6" Residential lots. It is fronted along Main Street by commercial establishments, zoned "C2" Commercial.

South: Undeveloped property zoned "R1-20" Residential, which is the subject of associated application DASZ 10/05.

East: The Red River bounds the property on the east.

West: To the immediate west is a commercial establishment and undeveloped property fronting Main Street zoned "C2" Commercial. Further west are residential properties zoned predominantly "R1-4" and "R1-5" Residential.

Adjoining Development Proposal: A second development proposal for lands to the south (DASZ/10) has also been received. As the two proposals have not been made jointly, they are being considered separately.

Description of the Proposed Development

Overview

The subject application constitutes infill development on an undeveloped parcel of land in the Rivergrove neighbourhood of the Old Kildonan Ward. The plan provides for the new development to be served by the southerly extension of Rivergrove Drive connecting with Main Street via a proposed new signalized intersection.

Lots
85 single-family residential lots, zoned "R1-4" Residential and .7 acres of public reserve land adjacent to the river zoned "PR1" Parks and Recreation are being proposed with this development. The gross density is 4.79 units per acre and the lot averages are as follows:
West of Rivergrove Drive 47.3 feet x 114 feet (5,392 square feet)
East of Rivergrove Drive 50.4 feet x 114 feet (5,745 square feet)

Streets
The proposed street alignment would include an east/west street (Attridge Lane) which would terminate in a cul-de-sac west of Rivergrove Drive and would tie into the street network of the proposed adjacent development (DASZ 10/05) east of Rivergrove Drive.

Dike
A portion of the proposed development is located within the City's designated "Floodway Fringe Area" and therefore requires flood protection as outlined in Floodway Fringe Area Regulation 266/91. To flood proof the area, the Developer is proposing to construct a primary dike. Any proposed primary dike construction must meet standards stipulated by the City and the Provincial Dyking Commissioner.

Public Input
Public Input was received by the applicant at two open houses which were held at Ecole River Bend on April 20, 2005 and May 12, 2005. Both open houses were well attended by the community.

Analysis

Plan Winnipeg
Under Plan Winnipeg 2020, the subject area is, in its entirety, within a Neighbourhood Policy Area. Neighbourhood Policy Areas are intended to include a residential mix together with a variety of educational, recreational, institutional, commercial and possibly industrial uses, at a scale and density compatible with each other. This development meets several key goals of Plan Winnipeg including *infilling of vacant lands* (3A-02 iv) and *supporting new development which is adjacent to, and compatible with, existing development* (3A-02v). There is a demonstrated need for new residential development in the area and recognition that infill lands, with existing service in place, are the best place to accommodate it. This subdivision represents an orderly expansion of residential development and a logical next step for the Rivergrove Neighbourhood to the north.

Another objective of Plan Winnipeg, and of equal importance, is the protection of environmentally sensitive lands that contain important pockets of natural flora and fauna by evaluating proposed new developments that impact high–quality natural areas and encouraging the protection and preservation of such lands to the greatest extent possible.

Issues
The Planning and Land Use Division supports the proposed infill residential development. However, there are several issues which remain unresolved and need to be evaluated in detail. These include, but are not limited to:

1. A lack of a secondary point of access
2. The length of the cul-de-sac (Attridge Drive) west of Rivergrove Drive
3. The location of the primary dike

1. Secondary Point of Access
In order to construct the southerly extension of Rivergrove Drive, which would connect with Main Street via a proposed new signalized intersection, a portion of an existing city-owned right-of-way, where it intersects with the proposed Rivergrove Drive right-of-way, is required to be opened as a street.




Figure 1: ROW and Easement Across Proposed Extension to Rivergrove Drive

At the same time, an adjacent property owner who is not a party to this application, holds an all-purpose easement across this right-of-way. In order for the street to be opened across this easement, the easement holder must agree to withdraw the easement, which the applicant has indicated has not occurred. Without agreement from this individual, this land cannot be opened at a street –preventing the crucial connection with Rivergrove Drive to the north and eliminating an essential second point of access to both this development and that to the south.

It should be noted that another means of opening the street is through expropriation by the City. This strategy is typically used only in extraordinary circumstances, can be problematic, and is generally not well received by the affected party.

Given the fact that this individual is not party to the application, any conditions requiring modifications to his land holdings may be impossible for the applicant to satisfy.

2. Length of Cul-de-sac
The cul-de-sac being proposed on Attridge Drive, is in excess of 250 metres in length, which is more that twice the City's guidelines of 105 metres for cul-de-sac length. This guideline has been established to facilitate maintenance of streets (plowing, street cleaning, etc) and for emergency access – in the event that the cul-de-sac in obstructed. The Public Works Department recommends that the cul-de-sac be reconfigured to provide a connection to extend southerly into the adjacent development, DASZ 10/05, so as to reduce the overall length of the cul-de-sac being proposed under this application.

3. ***Location of Primary Dike***
Adjacent to Riverbottom Forest
The applicant is proposing a top of dike location at the rear of the riverfront lots, with the riverside slope of the dike extending up to 65 feet into the designated public reserve land. The regrading and fill that will be required for the dike will destroy the majority of the trees in this area – leaving only a narrow strip adjacent to the river undisturbed.

Over the past 15 years, the City has had various subdivision designs and lot lines with respect to additions to the City's primary dikes. In the case of River Ridge, the entire primary dike is part of the lot, with the lot line being at the base of the dike on the riverside. The City has easements on these properties to provide access to the primary dike and caveats on the title to ensure that no structures are erected within the easement area. In this instance, the lots exceed 150 feet in depth – which provides adequate space for a rear yard in addition to the dike footprint.

In order to preserve as much of the river bottom forest as possible, a similar arrangement, at the request of the applicant, was deemed to be acceptable, provided that the primary dike is adequately protected through similar easements and caveats on private lands.

However, it appears as if this design is not possible given the current configuration of riverfront lots. To that point, the depth of riverfront lots, which is approximately 120 feet deep, is not adequate to accommodate the dike footprint– which requires up to 130 feet, in addition to the requirements for the house and front and rear yards.

The natural area that would be disturbed, while not containing the number of large sized cottonwoods and other species as the forest to the south, is likewise important in that it provides a connection between larger adjacent critical habitat areas to the north and south and provides for the preservation of this unique ecosystem by designating a larger contiguous area for protection. In that regard, Plan Winnipeg guides us to "*encourage the protection and preservation of high*

quality natural lands to the greatest extent possible." (Policy 5C-04) Therefore, the Planning and Land Use Division recommends that the plan be modified to provide lot depths which would permit the dike to be wholly located within private lots and to avoid all disturbances within the designated public reserve land.

Extending to the north

The applicant's plan proposes that the primary dike continue to extend north through adjacent properties, including City of Winnipeg property, all the way to Red River Boulevard where it would then jog west along the rear of private lots to its terminus. At this time, the applicant has not received authorization from the adjacent property owners (there are four separate owners to whom this would apply) to allow a dike to be constructed within their property. In the absence of authorization from effected property owners, this plan cannot be accepted. However, construction of the primary dike wholly within the applicant's property – which would look similar to the above noted arrangement but would be at the rear of private lots on the applicant's property, would be an acceptable solution and may allow for the ability to continue the primary dike to the north in the future at such time as adjacent property owners choose to develop their land. It should be noted that this option might again require that some or all of the effected lots be deepened to provide adequate space for the dike to be accommodated.

Recommendation

In light of the above, the Planning and Land Use Division is recommending that this item be adjourned until a future date to be determined by the applicant and the City jointly in that hope that additional time may bring resolution of issues to the satisfaction of the applicant and the City, so that this development may be proceeded with in the future in a modified form.

The Planning and Land Use Division recommend that the item be adjourned for the following reasons:

1. A second point of access cannot be provided until there is resolution with the easement across the road right of way.
2. The plan of subdivision will require modification to accommodate a southern connection to the cul-de-sac to reduce the length
3. The riverfront lot depths will require modification to accommodate the dike completely within the private lots – leaving no disturbances within the public reserve land.
4. The dike cannot be extended to the north because adjacent property owners have not provided authorization. An alternative dike alignment wholly contained within the applicant's property is required.

However, should the Community Committee wish to approve the application, the following conditions should be considered:)

Recommended Conditions of Approval

I. That the plan of subdivision proposed under File No. DASZ 11/05 be approved for preparation as a plan of subdivision by a Manitoba Land Surveyor in accordance with Schedule "A" for File No. DASZ 11/05, attached hereto and dated June 6, 2005, for registration in the Winnipeg Land Titles Office, subject to the following:

A. That the Developer be required to enter into a Development Agreement with the City containing all the conditions outlined in the report of the Administrative Coordinating Group dated May 31, 2005;

II. That the Director of Planning, Property and Development be authorized to certify any documents in connection therewith.

III That The Winnipeg Zoning By-Law No. 6400/94 be amended by rezoning the subject land as shown on Schedule "A" for File No. DASZ 11/05, attached hereto and dated June 6, 2005, to an "R1-4" Residential District and a "PR1" Parks and Recreation District.

IV. That, in the event the application is not proceeded with expeditiously and the by-law is not enacted within twenty-four (24) months after adoption of the report by Council, the matter shall be deemed to be concluded and shall not be proceeded with unless an extension of time is applied for prior to the expiry of this twenty-four (24) month period and the extension is subsequently approved by Council.

V. That the City Solicitor/Manager of Legal Services be requested to prepare the necessary by-law in accordance with the above.

VI. That the subdivision section of the by-law shall come into force and effect upon execution by the City of Winnipeg of the Development Agreement.

VII. That the zoning section of the by-law shall come into force and effect when the Plan of Subdivision has been registered in the Winnipeg Land Titles Office **provided that the said effective date occurs within twenty-four (24) months from the date that the said rezoning by-law is adopted by Council.**

VIII. The Plan of Subdivision shall be approved and signed by the Director of Planning, Property and Development within two (2) years of the date of passage of the aforementioned by-law.


IX. In the event that the necessary City of Winnipeg mylar approval signatures have not been secured within twenty-four (24) months after adoption of the by-law, the matter shall be deemed to be concluded and shall not be proceeded with unless Council extends that time.

This Report Submitted by:
Planning, Property and Development Department
Planning and Land Use Division

Report Prepared by: Michael Robinson, AICP
PPD File # 3.322

Revised Schedule "A"

By-Law No. _____	File No. **DASZ 11/05**
Atlas Sheet No. **S28** **LORD SELKIRK WEST KILDONAN COMMUNITY**	Explanation An application for the approval of the plan of subdivision shown outlined below and for a proposed zoning change to By-law No. 6400/94 by rezoning the land located on the east side of Main Street, south of Rivergrove Drive from an "R1-20" RESIDENTIAL DISTRICT to a "PR1" PARKS AND RECREATION DISTRICT and an "R1-4" RESIDENTIAL DISTRICT as shown outlined below.



Revised Schedule "A" to the report to the Lord Selkirk-West Kildonan Community Committee for File No. DASZ 11/05 dated June 16, 2005

THIRD READING : _____ EFFECTIVE DATE : _____

ZONING AGREEMENT : YES ☐ NO ☐ CAVEAT No. _____

Appendix 1
Aerial Photo (Flown in 2002)



Appendix 2
Zoning Map




Exhibit "11" referred to in File DASZ 11/2005

Re: Proposed subdivision and rezoning on land located on the east side of Main Street, north and south of Commonwealth Avenue – DASZ 11/05

An application has been submitted by Lombard North Group (David Palubeski) to subdivide and rezone land located on the east side of Main Street south of Commonwealth Avenue.

It is recommended that the plan be amended if and as required to comply to the following:

A. The proposed cul-de-sac west of Rivergrove Drive is to be reconfigured to provide a connection to extend southerly into the adjacent development, DASZ 10/05, so as to reduce the length of the cul-de-sac being proposed under this application, DASZ 11/05. The cul-de-sac being proposed is in excess of 250m in length which is more than twice the City's guideline for cul-de-sac length of 105m.
B. Rivergrove Drive is to be extended as a Public Street right-of-way from its existing terminus north of the proposed subdivision, southerly to the south limit of the proposed subdivision.
C. The proposed walkway at the west terminus of the proposed cul-de-sac west of Rivergrove Drive shall be deleted.
D. By including the river bottom forest as public open space to the satisfaction of the Director of Public Works and the Director of Water and Waste.
E. By adjusting the size of the lots adjacent to the proposed Primary Dike in order to accommodate the said dike within the private properties and to avoid encroachment into the river bottom forest to the satisfaction of the Director of Public Works and the Director of Water and Waste.

It is recommended that approval of the amended plan be subject to the Developer entering into a Development Agreement as follows:

1. The Developer shall pay its share of the cost of the following improvements at and in the vicinity of the intersection of Rivercrest Avenue and Main Street on an area basis, as determined by the Director of Public Works:

    a) a 3.5m in width by 40.0m in length southbound left turn storage lane, plus upstream transition and all related works;
    b) right-turn channelization in the southeast and northeast corners of the intersection, modifications to the existing median opening as may be required and modifications to Ridgecrest Avenue west of Main Street as may be required to be compatible with Ridgecrest Avenue east of Main Street and all related works;
    c) the full cost of the installation of traffic control signals and all related works, including, but not necessarily limited to, pedestrian and vehicular actuation, interconnection to adjacent traffic control signals and audible pedestrian signals;

2. The Developer shall pay to the City, in cash, on demand its share of the cost of the following services previously installed or to be installed by the City in Main Street:

    a) a 4.0m in width by 200mm in thickness portland cement concrete lane of pavement and related works;
    b) a 1.5m in width by 100mm in thickness portland cement concrete sidewalk in the east boulevard;

c) street lighting in the east boulevard;
d) landscaping in the east boulevard;

all as determined by the Director of Public Works.

3. The Developer shall, at no expense to the City, construct portland cement concrete pavement to widths of 7.5m and 10.0m and thicknesses of 150mm and 20mm respectively in all streets within the proposed subdivision, and all related works including, but not necessarily limited to boulevard landscaping and ornamental street lighting, all as determined by and to the satisfaction of the Director of Public Works.
4. The Developer shall, at no expense to the City, construct a portland cement concrete sidewalk to a width of 1.5m by 100mm in thickness on both sides of Rivergrove Drive, as determined by and to the satisfaction of the Director of Public Works.
5. The Developer shall, at no expense to the City, construct all watermains, wastewater sewers and land drainage sewers required to service the proposed subdivision and adjacent lands. Further, the Developer shall pay for its share of the regional land drainage system. The construction of any land drainage trunk works, as determined by the Director of Water and Waste, will be credited toward this charge.
6. The Developer shall provide a lot grading plan prepared by a municipal engineer and shall grant any easements as may be necessitated by the design.
7. The Developer is to pay all costs associated with the installation and/or relocation of street lights and other utilities made necessary as a result of or required to accommodate works, which are required by the Developer to serve the proposed subdivision, as determined by and to the satisfaction of the Director of Public Works.
8. The Developer shall be responsible to control and to initiate the clean up of litter and refuse from the contractors and builders for this development, both on-site and off-site, during the installation of services and construction of buildings, until substantial completion of all construction. The clean up of litter and refuse shall be done on a regular basis as determined by the Director of Public Works. This shall include initiating action and assuming any costs in remedying the situation to the satisfaction of the Director of Public Works.
9. The Developer shall ensure that construction traffic uses access routes as determined by the Director of Public Works. The Developer shall maintain, at no expense to the City, the access routes in a clean, dust free and safe condition, free of dropped and tracked-on mud, and shall undertake regular scarping and sweeping of streets until building construction, including landscaping is complete, all as determined by and to the satisfaction of the Director of Public Works.
10. The Developer shall, at no expense to the City, construct a portland cement concrete sidewalk to a width of 1.5m by 100mm in thickness on the both sides of Rivergrove Drive, as determined by and to the satisfaction of the Director of Public Works.
11. The Developer shall, at no expense to the City, construct a cul-de-sac type vehicle turnaround at the terminus of each temporarily dead-ended street and provide any right-of-way or easements necessary to accommodate same, all as determined by and to the satisfaction of the Director of Public Works.
12. The Developer shall, at no expense to the City, erect and maintain barricades and signing across the full width of any temporarily dead-ended streets, due to phasing of development, immediately upon completion of the paving or when house construction has begun, whichever is sooner, as determined by and to the satisfaction of the Director of Public Works.

13. The Developer shall ensure that two paved means of vehicular access are available at all times through all stages of development of the Planned Area to the satisfaction of the Director of Public Works. This may require the construction of temporary roadways and the provision of easements or right-of-way therefore.
14. The Developer shall, at no expense to the City, provide underground electrical and telephone services to serve the proposed subdivision and will pay the full cost to convert any existing overhead services within the proposed subdivision to underground.
15. There are to be no private approaches serving single or two family residential development off Rivergrove Drive.
16. The Developer shall, at no expense to the City, cause to be installed standard reflectorized permanent street name signs at each new intersection within or adjacent to the proposed subdivision, as determined by the Director of Public Works.
17. The Developer shall, at no expense to the City, construct a Primary Dike to protect the proposed development from flooding in accordance with the requirements of the Dyking Commissioner and the Director of Water and Waste. This shall include constructing the dike to the 1:700 year flood protection level (with expanded Floodway) and installing riprap as required to arrest shoreline erosion and protect the long-term performance of the dike. All plans and specifications for the proposed Primary Dike shall be submitted to the Water and Waste Department for review and approval prior to the release of the subdivision mylars.
18. The Developer shall dedicate approximately 4% of the land within the proposed subdivision as public open space and shall pay cash to satisfy the approximately 4% remaining dedication requirement. The Developer shall also pay cash for landscaping and servicing of public open space in accordance with City policy.
19. The Developer shall pay the full cost of engineering services provided by or on behalf of the City in connection with the installation of all services required to serve the proposed subdivision.
20. The Developer shall pay $1,200.00/acre to defray the City's administration and related costs associated with the preparation and implementation of the development agreement.

THIS REPORT SUBMITTED BY:

Administrative Coordinating Group
File No. AG 11/05
May 31, 2005

"Original signed by E.L. Carrière"
Land Development Engineer

"Original signed by K.T. Raban"
Water and Waste Department

"Original signed by R.J. Hartmann"
Public Works Department
Transportation Division

Exhibit "16" referred to in File DASZ 11/2005

THIS IS EXHIBIT "16" REFERRED TO
IN FILE NO. DASZ 11/05
DATED THIS 14 DAY OF June 20 05
D. Jennings
CLERK

LOMBARD NORTH GROUP (1984) LTD.

PLANNERS AND LANDSCAPE ARCHITECTS

June 14, 2005

Submitted by
David Palubeshi
on June 14, 2005

Chair and Members
Lord Selkirk Community Committee
CITY Hall
510 Main Street
Winnipeg, Manitoba

RE: DASZ 10/05 and DASZ 11/05 Subdivision and Re-Zoning Application Plan

We have reviewed with our clients the City's strong desire to preserve more river bottom forest area than presently provided in the plan reviewed by community stakeholders in our second open house and submitted for consideration at today's public hearing by the West Kildonan-Lord Selkirk Community Committee.

In an effort to reconcile city wants and the economics of the developer's project, we looked at ways we could propose an alternate plan which increases open space dedication and does not compromise the potential economics of the project. We have developed an alternate plan for consideration. The alternate plan has been approved for presentation to the City by our Clients' Greenview Homes (DASZ 10/05) and Coral Reef Developments (DASZ 11/05).

The attached Amended Plan increases open space dedication from the original 7.1 acres to 9.8 acres. The additional open space dedication is composed of entirely river bottom forest area and increases the area of river bottom forest excluded from residential and dike development to 4.9 acres from 3.1 acres.

The cumulative changes made to our client's project to accommodate city open space river bottom forest requests represent:

- an open space dedication of 24%, over the Greenview net holdings after deducting the high school site;
- the loss of 884 feet of residential development frontage;
- increased dike length and construction costs; and

'SERVING COMMUNITIES, GOVERNMENT AND BUSINESS SINCE 1968'

505-93 LOMBARD AVE. WINNIPEG MANITOBA CANADA R3B 3B1
TEL (204) 943 3896 FAX (204) 947 5696
www.lombardnorth.com

- Additional unanticipated property development coordination expenses.

The neighbourhood planning challenge for both the City and Developer will be to bridge the gap between City wants and Developer financial resources given the stated position that the city has no funds to compensate the developer for the loss of the additional river bottom forest dedication.

Our clients' agreement to consider providing the additional river bottom forest and open space dedication substantially in excess of that conventionally sought by the City, is offered with the expectation they will receive considerations of a value from the City that re-balances the financial impact of dedication on the project. Our clients are aware compensation has been provided by the city in similar situations elsewhere in the City.

It possible for the City to provide credits under the Development Agreement which re-balances the economics of the project after expanding dedication without costs incurred by the city for compensation.

Our clients will proceed with the amended plan subject to approval of the following adjustments to the terms and condition of the ACG report dated June 7, 2005 as it relates to DASZ 10/05:

ACG Proposals for Plan Amendment DASZ 10/05:

Developer response to the ACG proposals for amending the plan of subdivision DASZ 10/05:

A. **Agree**- Developer shall provide rights of ways corner cuts at Ridgecrest and Main Street.

B. **Disagree –** Main Street has been widen and redeveloped as a four lane divided Arterial Street over 16 years ago with side walks and boulevard development we disagree there is a need to widen Main Street by 2.743 meters at this time.

C. **Agree –** Provide the 32 meter right of way and 60 meter transition for Ridgecrest Street extension east of Main Street.

D. **Disagree**- Community information meetings have confirmed there is no support for a 170 meter radius curve for Ridgecrest Street's connection with Rivergrove Dr. The High School and associated day care prefer the "L" intersection as a traffic calming technique by the school grounds. We will however design the radius of the street curve at the "L"

'SERVING COMMUNITIES, GOVERNMENT AND BUSINESS SINCE 1968'

505-93 LOMBARD AVE. WINNIPEG MANITOBA CANADA R3B 3B1
TEL (204) 943 3896 FAX (204) 947 5696
www.lombardnorth.com

intersection to ensure easy maneuvering for large vehicle turning.

E. **Agree** – To provide frontage roads as illustrated in the plan of subdivision with 9 meter right –of ways.

F. **Disagree** – Reconfiguration of the proposed Greenview cul-de-sac (Marydale Place) into a bay connecting to DASZ 11/05 proposed Attridge Lane is unacceptable because of the impact on lots. It is noted that DASZ11/05 provides an emergency access to Commonwealth from Attridge Lane.

G. **Agree with Modification** – Developer agrees to alter the plan and open space dedication to increase the river bottom forest dedication from 3.1 to 4.9 acres as illustrated in the Amended Plan attached hereto and request Community Committee of the Amended Plan for DASZ10/05 and related plan adjustments for DASZ 11/05.

H. **Agree** – Developer will extend the depth of the lots backing onto the dike so as to include the dike entirely within private property and agrees to register an easement over that portion of the dike representing the 4 meter crown and river side slope to permit City access for its purposes and to ensure compatible landscape development.

ACG Proposals for Plan Amendment DASZ 11/05:

Developer response to the ACG proposals for amending the plan of subdivision DASZ 11/05:

A. **Disagree**- Developer shall provide a secondary emergency access to Commonwealth from the east end of the proposed Attridge Cu-de-sac.
B. **Agree** – To connect Rivergrove Drive to subdivision with city's cooperation (as the land owner) and John Whiteway as the easement holder.
C. **Disagree** – Walkway to be developed as emergency access to Cul-de-sac.
D. **Agree with Modification** – To provide river bottom forest as illustrated in Amended Plan
E. **Agree** – Dike lot depth to be as in DASZ 11/05.

ACG Terms of Approval DASZ 10/05

In regard to ACG terms of development approval for DASZ 10/05 we request approval of the following adjustments in recognition of the

'SERVING COMMUNITIES, GOVERNMENT AND BUSINESS SINCE 1968'

505-93 LOMBARD AVE. WINNIPEG MANITOBA CANADA R3B 3B1
TEL (204) 943 3896 FAX (204) 947 5696
www.lombardnorth.com

financial impacts of the dedication requests made of the developer to preserve the river bottom forest area:

1. **Agree In Part** - The developers' responsibilities for their share of improvements at the intersection of Ridgecrest Avenue and Main Street be modified to:

    a) **exclude** contribution to the 3.5m by 40 m in length south bound left turn storage lane including up –stream storage These were previously installed by the City a number of years ago;
    b) **agree** to right turn channelization and modification to Ridgecrest on east of Main Street; exclude the cost of Ridgecrest modification west of Main Street. and to
    c) **Agree to provide a 50% contribution** not full cost of installing traffic control signals and related works including pedestrian and vehicle actuation, interconnection to adjacent signals and audible pedestrian signals at Main and Ridgecrest Intersection.

2. **Agree** - as modified under comments related to item #1 above with the understanding that the contribution towards costs benefiting the area east of Main Street be allocated on an area basis after deducting dedication lands.

3. **Exclude-** The developers not be required to pay for services previously installed in Main Street by the City. These services include;

    a) a lane of pavement 4.0m in width by 200mm in thickness and related works;
    b) a sidewalk in the east boulevard,
    c) street lighting and
    d) landscaping in the east boulevard;

4. **Agree** – to concrete pavement standards and related works;

5. **Agree**- sidewalk requirements.

6. **Agree** – Frontage road standards

7. **Agree**- Street sign standards

8. **Agree**- Cul-de-sac turn around standards

9. **Agree** – To temporary barricades and related works.

10. **Agree as Modified** – To providing two means off access to project development phases prior to school and house occupancy.

11. **Agree** – To underground utility services.

12. **Agree** – To street light and utility relocation costs as required.

'SERVING COMMUNITIES, GOVERNMENT AND BUSINESS SINCE 1968'

505-93 LOMBARD AVE. WINNIPEG MANITOBA CANADA R3B 3B1
TEL (204) 943 3896 FAX (204) 947 5696
www.lombardnorth.com

13. **Agree** – To site litter management and clean up during construction of services and houses;

14. **Agree** – to the designation of a construction traffic route.

15. **Agree as Modified** – To construction of underground services and outfall. It being agreed any over-sizing of city services benefiting other lands will be apportioned among land owners after netting out open space land dedication.

16. **Agree in part** – Developer to construct the primary dike to the 1:700 year flood. **Exclude as a developer obligation the installation rip-rap** along the south riverbank shoreline. The location of the dike has been designed by the developers' engineers UMA , to provide a 100 year riverbank erosion safety margin, assuming historical erosion rates quantified for the last 50 years continue into the future;

17. **Agree** – Lot grading plans

18. **Agree** – to pay full cost of engineering services.

19. **Exclude** – Developer to be forgiven the City's administration charge of $1,200 per acre for the development agreement implementation.

20. **Agree** – the Developer undertakes to dedicate more than 10 % dedication of land as shown in the Amended Plan as attached hereto.

ACG Terms of Approval DASZ 11/05

In regard to ACG terms of development approval for DASZ 11/05

The terms of approval for DASZ 11/05 numbered items 1 to 20 inclusive are similar to the terms for DASZ 10/05 (although the numbering system is slightly different. The developer's position on the terms of approval for similar items is the same for DASZ 11 as for DASZ 10 /05. The DASZ 11/05 developer Coral Reef Holdings wishes to confirm under ACG item #18 that dedication lands shall be as illustrated in the Amended Plan and any cash dedication payable under DASZ11/05 be allocated to assist defray open space costs in DASZ 10/05.

Additional Proposals by the Developer of DASZ 10/05

21. The Developer will contribute towards shoreline rip rap in exchange for City lands fronting Red River Boulevard and located east of Rivergrove Dive

22. The City assume maintenance responsibility for the riverbank park and river bottom forest upon registration of the plan of subdivision and maintenance responsibility for the other dedicated open space areas after landscape, walkway and play structure improvements

'SERVING COMMUNITIES, GOVERNMENT AND BUSINESS SINCE 1968'

505-93 LOMBARD AVE. WINNIPEG MANITOBA CANADA R3B 3B1
TEL (204) 943 3896 FAX (204) 947 5696
www.lombardnorth.com

have been completed subject to standard contractor warranties for good workmanship;

23. The Developer's responsibility for trail development within the River bottom forest area be limited to the cost of developing a low impact natural trail to be designed in consultation with the City Naturalist and located below the elevation of the crest of the dike;

24. The City agrees that any cash dedication that may be payable from DASZ 11/05 or cash dedication from future development of other private lands within the RiverRidge Concept Plan area will be earmarked for investment in the RiverRidge open space network in order to assist fund:
    - develop the pathways and sidewalks linking RiverRidge neighbourhoods to the river park and proposed high school sports grounds;
    - open space landscaping, lighting and a children's play structure; and to
    - develop river bank pathway connections linking RiverRidge to McBeth Park, Rivergrove and Kildonan Park;

25. The allocation of infrastructure costs such as the trunk land drainage sewers, stormwater outfall, the Ridgecrest and Main Street intersection works, including right turn channelization in the southeast and northeast corners of the intersection be apportioned among the RiverRidge development lands based upon the calculation of net developable area after deducting open space dedication lands;

26. The Developer has had discussions with private property owners to extend the primary flood protection dike across private lands north of the development areas represented by DASZ 10/05 and DASZ 11/05. This may be completed by way of easement now and later by way of dedication as these private lands are developed in the future. It is important for the purpose of securing private property owner approvals for alignment of the dike that we confirm in principle the dike route as part of DASZ 10 and 11/05. Therefore we request the City confirm in principle its agreement to:

    i) Approve the primary dike extension onto private lands as generally illustrated in the alternate plan attached;
    ii) Register a dike easement agreement and to cooperate with the developers and three private property owners (Lehmann, Whiteway and Draco Developments) located north of the development areas represented in DASZ 10 and 11/05, in coordinating the registration of the private dike easements;
    iii) Approve the alignment of the primary dike across city lands as illustrated in the Amended Plan and located on the south side of Red River Boulevard
    iv) Recover for reimbursement to the Developers' of DASZ 10 and 11/05 the proportionate share of dike construction costs as certified by the project engineer and benefiting the three aforementioned private land owners.

'SERVING COMMUNITIES, GOVERNMENT AND BUSINESS SINCE 1968'

505-93 LOMBARD AVE. WINNIPEG MANITOBA CANADA R3B 3B1
TEL (204) 943 3896 FAX (204) 947 5696
www.lombardnorth.com

27. The subdivision changes represented by the Amended Plan attached hereto do not prejudice the rights of any person and the plan as advertised may be corrected to reflect the Amendments agreed.

I wish to thank you in advance for your consideration of our clients' Amended Plan. Timing is of critical importance to our clients in order to assist the Seven Oaks School Division meet its timeframe for school construction start. We would be very grateful to receive approval of the Amended Plan by Council's committees so that we may receive concurrent with committee report approvals, the approval of the related by-laws for the plan of subdivision and zoning at Council's July 27th 2005 meeting.

Yours truly,
Lombard North Group (1984) Ltd.,



David Palubeski, M.C.I.P.
President

Attach.

'SERVING COMMUNITIES, GOVERNMENT AND BUSINESS SINCE 1968'

505-93 LOMBARD AVE. WINNIPEG MANITOBA CANADA R3B 3B1
TEL (204) 943 3896 FAX (204) 947 5696
www.lombardnorth.com

Exhibit "17" referred to in File DASZ 11/2005

