Zero Scape Quote

Urban Empire Landscape & Construction

Client Name:	Rick Stephanchew
Project Name:	453 Marion Street | Rick Stephanchew
Jobsite Address:	453 Marion Street Winnipeg, Manitoba R2H 0V6
Billing Address:	453 Marion Street Winnipeg, Manitoba R2H 0V6
Estimate ID:	EST1507884
Date:	Aug 28, 2019

Rock Planting Bed

Planting bed will include:

-6" of 4 way mix soil

-Geotextile cloth to separate soil from top cover

-Black granite will be spread 3" thick over top of the fabric

-Plants will be added backed by a 2 year warranty

-Vinyl edging will be installed to separate planting bed from the limestone

All backed by a two year warranty

*** Planting bed will be maintenance free creating a zero scape zone***

Gravel Strip

Gravel Strip will include:

-We will remove existing gravel and soil digging 4 inches down beside the sidewalk

-Adding geotextile cloth to prevent rocks going through the soil profile

-We will supply, spread and level 3/4" limestone rock 4" thick and compact area

***Doing this will create a buffer zone allowing it to be a maintenance free zone "Zero Scape" ***

Subtotal	$2,443.21
Taxes	$177.07
Estimate Total	**$2,620.28**

115 Shier Dr
p. 2047926168
Winnipeg, Manitoba Manitoba
email: info@urbanempire.ca

Estimate authorized by: _____

Company Representative

Signature Date: _____

Estimate approved by: _____

Customer Representative

Signature Date: _____

115 Shier Dr
Winnipeg, Manitoba Manitoba
p. 2047926168
email: info@urbanempire.ca

Mayer Landscape Design

453 Marion St

780 Foxgrove Avenue
Winnipeg, Manitoba

(204) 250-4804

Black Granite Planting Bed	Planting bed will be graded and sloped towards the street adding 6" of 4 way mix soil adding geotextile cloth over the soil adding 4 inches of 1" ½ black granite	$1,840.56
Gravel Strip	Gravel strip will be 3' from the sidewalk adding 4" of crushed limestone to create a buffer zone and a low maintenance area	$1,259.67
	Taxes	289.34$
	Total:	$3,389.57