**Appendix E - Rank**

| Rank | Score<br>Out of 500 | Region/ Summary of Improvements | Year 2030<br>Class 4 Estimate |
|---|---|---|---|
| 1 | 415 | <u>Youville Curve – connecting westbound Marion to Goulet</u><br>• Primarily a traffic safety improvement related to the tight S-curve that connects Marion to Goulet.<br>• Includes safe pedestrian and active transportation (AT) crossings as AT transitions from unidirectional bike lane in the Marion – Goulet couplet to a multiuse path further east on the south side of Marion. | $10.3 M |
| 2 | 360 | <u>Marion – Goulet Couplet – St. Mary's Road to Youville</u><br>• Complete streets approach to provide a better balance for neighborhood livability while allowing safe and efficient throughput of traffic.<br>• Includes protected unidirectional bike lanes, wider pedestrian areas with bump-outs to better define parking lanes, calm traffic and reduce pedestrian crossing distances.<br>• Pavement renewal and complete street improvements on Goulet – Youville to Traverse was completed in 2024. Similar work for Goulet – Traverse to Tache is programmed for 2026. Both of these works have been deducted from the 2030 Class 4 estimate. | $27.0 M |
| 3 | 340 | <u>Marion – Archibald Intersection</u><br>• Intersection improvements for safety, traffic flow and accommodation of active transportation.<br>• Improvements to reduce operational safety concerns include centre medians, smart channels and changes to access management for several businesses.<br>• Replacement of box culvert on Dugald Drain under Archibald and the Tim Horton's access is required along with other drainage improvements. | $29.1 M |
| 4 | 295 | <u>Marion at Dawson and Panet Intersections</u><br>• Safety and traffic flow improvements include a median and left turn bay along Marion, as well as removal of the right turn cut-off southbound Dawson to westbound Panet.<br>• Improvements at this location are contingent on combined sewer separation occurring first. | $20.2 M |

| | | | |
|---|---|---|---|
| 5 | 250 | <u>Marion – Lagimodiere -Dugald</u><br><br>• Widen Lagimodiere to six lanes between Marion and Dugald including safety and traffic flow improvements at both intersections<br>• Improvements at this location are contingent on combined sewer separation occurring first. | $46.7 M |