APPENDIX B

REPORT OF THE ADMINISTRATIVE COORDINATING GROUP

RE: PROPOSED SUBDIVISION AND REZONING OF LAND LOCATED AT 158 OXFORD STREET

The Administrative Coordinating Group (ACG) has reviewed the servicing requirements for DAZ 227/2025. The applicant is advised to take into consideration the following servicing and design requirements in preparing the redevelopment plans for the site:

Section I – General Comments

1. The Water and Waste Department (WWD) advises that there is adequate servicing capacity for the proposed development based on the submitted development plans. Should the development plans change, WWD will need to review the revised proposal.

2. The subject land is located in a combined sewer district. In accordance with Clause 8 of Environment Act Licence 3042, any development on the land cannot result in an increase in flow into the combined sewer. Typically, increases in wastewater discharge may be offset by a reduction in land drainage discharge from the property.

   At the site servicing design stage, the discharge from the proposed future development into the combined sewer must not exceed the allowable discharge rate:

   a) The allowable discharge rate shall be the sum of the existing peak wastewater and the peak land drainage discharged.

   b) The peak land drainage discharged from the site must be based on a c-value of 0.35, with a 5-year rainfall event applied.

   c) The existing and proposed peak wastewater discharge must be estimated using the Wastewater Flow Estimation Guidelines published on the City of Winnipeg website (http://winnipeg.ca/waterandwaste/dept/wastewaterFlow.stm), unless otherwise approved.

THIS REPORT SUBMITTED BY:

Administrative Co-ordinating Group
File No. DAZ 227/2025
January 30th, 2026

"*Original Signed by K. Kowalyk"*
K. Kowalyk, P. Eng.
Land Development Branch, Planning, Property and Development Department

"*Original Signed by M. Gajda"*
M. Gajda, P. Eng.
Engineering Division, Water and Waste Department